

Power Quality Enhancement Techniques in Hybrid AC/DC Microgrid Analysis and Implementation

Sumit Kumar¹, Ashish Bhargava²

¹Student, ²Professor,

^{1,2}Bhabha Engineering Research Institute, Bhopal, Madhya Pradesh, India

ABSTRACT

Distributed generators (DGs) that rely on renewable energy sources have become more important in the face of rising global temperatures. Substantial impetus will soon be supplied by wind, solar energy, biomass, mini-hydro, and the use of fuel cells and microturbines. Distributed generation, where electricity is produced by a number of different renewable and unconventional energy sources, has emerged as a viable option for the construction of modern electrical systems because to its low environmental impact, scalability, and adaptability. A microgrid is a small-scale electrical grid in which multiple loads and distributed generators are coordinated under a single set of controls. Microgrids are a kind of integrated energy delivery system that may either work in tandem with the main power grid or operate autonomously. The concept of a microgrid eliminates the need for several inverters in a single AC or DC grid and simplifies the connection of intermittent, renewable AC and DC power sources and loads. Equipment safety and security issues have been brought to light by the power electronic converters that link DGs to the utility/grid. Greater local dependability, lower feeder losses, local voltage support, increased efficiency through waste heat use, voltage sag correction, and uninterruptible power supply are only some of the configuration options available to the client for the microgrid. In this study, we analyse the functionality of a hybrid AC/DC microgrid while connected to the mains power supply. A solar array, a wind generator, and a battery are used to build a microgrid. The converters can now properly coordinate the AC and DC sub-grids thanks to the added control techniques. Results were obtained by use of the MATLAB/SIMULINK software environment.

How to cite this paper: Sumit Kumar | Ashish Bhargava "Power Quality Enhancement Techniques in Hybrid AC/DC Microgrid Analysis and Implementation" Published in International Journal of Trend in Scientific Research and Development (ijtsrd), ISSN: 2456-6470, Volume-6 | Issue-6, October 2022, pp.1972-1987,

www.ijtsrd.com/papers/ijtsrd52196.pdf



URL:

Copyright © 2022 by author (s) and International Journal of Trend in Scientific Research and Development Journal. This is an Open Access article distributed under the terms of the Creative Commons Attribution License (CC BY 4.0) (<http://creativecommons.org/licenses/by/4.0>)



KEYWORDS: Solar (PV), Wind Energy (WECS), Hybrid System, AC/DC Microgrid, Distributed Generators, Power Enhancement, Stability, DFIG

1. INTRODUCTION:

There are a number of noteworthy changes in electric distribution technologies that will alter the needs of energy delivery as we go into the next century. Both the demand and supply sides are pushing for these adjustments, with the latter requiring changes to account for distributed generation and peak-shaving technology [1]. This is because both the demand and supply sides want more reliable and efficient energy.




Fig 1.1. Microgrid power system

As a consequence of deregulation and the proliferation of distributed energy supplies, power networks are undergoing profound changes in their operational needs (DER). Many DERs take use of RES like solar, wind, or hydro power, while others rely on other technologies that allow for microgeneration. Advantages include reducing transmission losses and avoiding network congestion, both of which are enhanced by placing micro sources in close proximity to the load. Also, since neighbouring micro sources, controllable loads, and energy storage systems can run in the islanded mode in the event of severe system disturbances, the likelihood of end-customers connected to a low voltage (LV) distribution grid (in Europe 230 V and in the USA 110 V) losing power supply is reduced. These systems are now known as microgrids. Microgrids are shown in Figure 1.1. This unique microgrid is about the same size as a low voltage distribution feeder and has a maximum capacity of 1 MVA and a range of around 1 km. More than ninety percent of low-voltage residential clients are typically served by subterranean cable, with the remaining ten percent provided via overhead lines. Microgrids often use combined heat and power plants (CHP), gas turbines, fuel cells, photovoltaic (PV) systems, wind turbines, etc. to provide both electricity and heat to its clients. Batteries and flywheels are common forms of energy storage [2]. The microgrid's energy storage system is analogous to the traditional grid's rotating reserve of big generators in that it maintains power stability, particularly at peak demand or when there are sudden shifts in supply or demand [3].

Microgrids may benefit customers in a number of ways, including meeting their thermal and electrical needs, decreasing emissions, increasing power quality by smoothing out voltage fluctuations, and decreasing overall supply costs. From the perspective of utilities, the use of decentralised energy sources has the potential to lower the need for transmission and distribution infrastructure. Distributed generation that is geographically near to loads has two major benefits: it may mitigate losses and it can possibly replace infrastructure in the transmission and distribution networks. Furthermore, having generation near to demand might improve the quality of service experienced by end users. Microgrids may help the network out by reducing congestion and speeding up the repair process after an outage. Emissions may be reduced and climate change mitigated with the help of newly developed microgrids. This is because technologies based on renewable sources and micro sources, which are characterised by extremely low emissions, are readily available and are emerging for distributed generating units [4].

Microgrids provide numerous benefits to consumers, utilities, and society as a whole, including enhanced energy efficiency, decreased overall energy consumption, lower emissions of greenhouse gases and other pollutants, higher service quality and reliability, and lower replacement costs for electricity infrastructure[2].

There are significant technical hurdles associated with microgrid operation and controls. Improving complex control techniques for microgrid inverters is necessary to provide stable operation during network disruptions, maintain stability and power quality in the islanding mode of operation, and supply stable frequency and voltage in the presence of arbitrarily fluctuating loads [4]. Because of this, the idea of a microgrid has piqued the interest of many scientists and policymakers in the United States, Europe, and Japan. Although microgrids hold great promise, their integration and operation are fraught with challenges.

FEATURES OF MICROGRID THAT REPRESENT TECHNICAL DIFFICULTIES

The protection mechanism for a microgrid, which must respond to failures on both the main grid and the microgrid, is a significant obstacle. To safeguard the microgrid loads in the first scenario, the protection system must quickly disconnect the microgrid from the main grid; in the second scenario, the protection system must isolate the tiniest possible section of the microgrid after the fault is cleared [30]. Micro source and load controllers are necessary for a microgrid's segmentation, or the creation of several islands or sub-microgrids. Selectivity (false, unneeded tripping)

and sensitivity (undetected faults or delayed tripping) issues with the protection system may become problematic under certain circumstances. There are two primary concerns when it comes to microgrid protection: the first involves the number of distributed energy resource (DER) units installed in the microgrid, and the second involves the availability of a sufficient level of short-circuit current in the islanded operating mode of microgrid, given that this level may substantially drop down after a disconnection from a rigid main grid. The authors of [30] calculated short-circuit currents for radial feeders equipped with DER and investigated the fact that the short-circuit currents used by over-current (OC) protection relays are location- and DER-specific. The circumstances will create deviations in the short circuit current's direction and magnitude. Given the nature of micro sources (wind and sun) and periodic demand change, the actual operating conditions of a microgrid are dynamic and ever-changing. It is possible to often alter the network's topology in an effort to decrease loss or accomplish other financial or operational goals. In addition, defects in such an in grid or in side microgrid might cause the formation of controlled islands of varying size and content. Since a result, generic OC protection with a single setting group may become inadequate, as it will no longer ensure a selected operation for all conceivable faults, and may cause a loss of relay coordination. Therefore, it is crucial to make sure that the OC protection relays' settings accommodate for the layout of the grid and any shifts in the location, type, or quantity of available generation. Otherwise, unintended behaviour or failure could occur under required circumstances. Microgrids dominated by micro sources with power electronic interfaces necessitate a new protection philosophy, where setting parameters of relays must be checked/updated periodically to ensure that they are still appropriate to deal with bi-directional power flows and low short-circuit current levels.

2. PHOTOVOLTAIC SYSTEM AND WIND ENERGY SYSTEM (DFIG)

Photovoltaic system

The photoelectric effect was first noted by French physicist Edmund Becquerel in 1839. He proposed that certain materials have property of producing small amounts of electric current when exposed to sunlight. In 1905, Albert Einstein explained the nature of light and the photoelectric effect which has become the basic principle for photovoltaic technology. In 1954 the first photovoltaic module was built by Bell Laboratories.

A photovoltaic system makes use of one or more solar panels to convert solar energy into electricity. It

consists of various components which include the photovoltaic modules, mechanical and electrical connections and mountings and means of regulating and/or modifying the electrical output.

Photovoltaic arrangements

Photovoltaic cell




Fig 2.1. Basic structure of PV Cell

The basic ingredients of PV cells are semiconductor materials, such as silicon. For solar cells, a thin semiconductor wafer creates an electric field, on one side positive and negative on the other. When light energy hits the solar cell, electrons are knocked loose from the atoms in the semiconductor material. When electrical conductors are connected to the positive and negative sides an electrical circuit is formed and electrons are captured in the form of an electric current that is, electricity. This electricity is used to power a load. A PV cell can either be circular or square in construction.

Photovoltaic module

Because of the low voltage generation in a PV cell (around 0.5V), several PV cells are connected in series (for high voltage) and in parallel (for high current) to form a PV module for desired output. In case of partial or total shading, and at night there may be requirement of separate diodes to avoid reverse currents. The p-n junctions of mono-crystalline silicon cells may have adequate reverse current characteristics and these are not necessary. There is wastage of power because of reverse currents which directs to overheating of shaded cells. At higher temperatures solar cells provide less efficiency and installers aim to offer good ventilation behind solar panel. Usually there are of 36 or 72 cells in general PV modules. The modules consist of transparent front side, encapsulated PV cell and back side. The front side is usually made

up of low-iron and tempered glass material. The efficiency of a PV module is less than a PV cell. This is because of some radiation is reflected by the glass cover and frame shadowing etc.

Photovoltaic array

A photovoltaic array (PV system) is an interconnection of modules which in turn is made up of many PV cells in series or parallel. The power produced by single module is not enough to meet the requirements of commercial applications, so modules are connected to form array to supply the load. In an array the connection of the modules is same as that of cells in a module. The modules in a PV array are usually first connected in series to obtain the desired voltages; the individual modules are then connected in parallel to allow the system to produce more current. In urban uses, generally the arrays are mounted on a rooftop. PV array output can directly feed to a DC motor in agricultural applications.




Fig 2.2. Photovoltaic system

Working of PV cell

The basic principle behind the operation of a PV cell is photoelectric effect. In this effect electron gets ejected from the conduction band as a result of the absorption of sunlight of a certain wavelength by the matter (metallic or non-metallic solids, liquids or gases). So, in a photovoltaic cell, when sunlight hits its surface, some portion of the solar energy is absorbed in the semiconductor material.




Fig 3.3. Working of PV cell

The electron from valence band jumps to the conduction band when absorbed energy is greater than the band gap energy of the semiconductor. By these hole-electrons pairs are created in the illuminated region of the semiconductor. The electrons created in the conduction band are now free to move. These free electrons are enforced to move in a particular direction by the action of electric field present in the PV cells. These electrons flowing comprise current and can be drawn for external use by connecting a metal plate on top and bottom of PV cell. This current and the voltage produces required power.

Wind turbines

With the use of power of the wind, wind turbines produce electricity to drive an electrical generator. Usually wind passes over the blades, generating lift and exerting a turning force. Inside the nacelle the rotating blades turn a shaft then goes into a gearbox. The gearbox helps in increasing the rotational speed for the operation of the generator and utilizes magnetic fields to convert the rotational energy into electrical energy. Then the output electrical power goes to a transformer, which converts the electricity to the appropriate voltage for the power collection system. A wind turbine extracts kinetic energy from the swept area of the blades.

DFIG system

The doubly fed induction machine is the most widely machine in these days. The induction machine can be used as a generator or motor. Though demand in the direction of motor is less because of its mechanical wear at the slip rings but they have gained their prominence for generator application in wind and water power plant because of its obvious adoptability capacity and nature of tractability. This section describes the detail analysis of overall DFIG system along with back-to-back PWM voltage source converters.

3. SYSTEM DESIGN AND IMPLEMENTATION AC/DC MICROGRID

The concept of microgrid is considered as a collection of loads and micro sources which functions as a single controllable system that provides both power and heat to its local area. This idea offers a new paradigm for the definition of the distributed generation operation. To the utility the microgrid can be thought of as a controlled cell of the power system. For example, this cell could be measured as a single dispatch able load, which can reply in seconds to meet the requirements of the transmission system. To the customer the microgrid can be planned to meet their special requirements; such as, enhancement of local reliability, reduction of feeder losses, local voltages support, increased efficiency through use waste heat,

voltage sag correction [3]. The main purpose of this concept is to accelerate the recognition of the advantage offered by small scale distributed generators like ability to supply waste heat during the time of need [4]. The microgrid or distribution network subsystem will create less trouble to the utility network than the conventional microgeneration

Configuration of the hybrid microgrid

if there is proper and intelligent coordination of micro generation and loads [5]. Microgrid considered as a 'grid friendly entity' and does not give undesirable influences to the connecting distribution network i.e. operation policy of distribution grid does not have to be modified[7].




Fig 3.1. A hybrid AC/DC microgrid system

The configuration of the hybrid system is shown in Figure 3.1 where various AC and DC sources and loads are connected to the corresponding AC and DC networks. The AC and DC links are linked together through two transformers and two four quadrant operating three-phase converters. The AC bus of the hybrid grid is tied to the utility grid.




Figure 3.2 describes the hybrid system configuration which consists of AC and DC grid.

The AC and DC grids have their corresponding sources, loads and energy storage elements, and are interconnected by a three phase converter. The AC bus is connected to the utility grid through a transformer and circuit breaker.

In the proposed system, PV arrays are connected to the DC bus through boost converter to simulate DC sources. A DFIG wind generation system is connected to AC bus to simulate AC sources. A battery with bidirectional DC/DC converter is connected to DC bus as energy storage. A variable DC and AC load are connected to their DC and AC buses to simulate various loads.

PV modules are connected in series and parallel. As solar radiation level and ambient temperature changes the output power of the solar panel alters. A capacitor C_{pv} is added to the PV terminal in order to suppress high frequency ripples of the PV output voltage. The bidirectional DC/DC converter is designed to maintain the stable DC bus voltage through charging or discharging the battery when the system operates in the autonomous operation mode. The three converters (boost converter, main converter, and bidirectional converter) share a

common DC bus. A wind generation system consists of doubly fed induction generator (DFIG) with back to back AC/DC/AC PWM converter connected between the rotor through slip rings and AC bus. The AC and DC buses are coupled through a three phase transformer and a main bidirectional power flow converter to exchange power between DC and AC sides. The transformer helps to step up the AC voltage of the main converter to utility voltage level and to isolate AC and DC grids.

Modeling and control of DFIG

This section explains the detailed modeling of DFIG. The state space equations are considered for induction machine modeling. The parameters and specifications of the DFIG are given in table 3.1. Flux linkages are used as the state variables in the model. Here two back to back converters are used in the rotor circuit. The main purpose of the machine-side

converter is to control the active and reactive power by controlling the d-q components of rotor current, while the grid-side converter controls the dc-link voltage and ensures the operation at unity power factor by making the reactive power drawn by the system from the utility grid to zero.

Two back to back converters are connected to the rotor circuit is shown in Fig 3.3. The firing pulses are given to the devices (IGBTs) using PWM techniques. Two converters are linked to each other by means of dc-link capacitor.





Fig. 3.3. Overall DFIG system

4. RESULTS

A hybrid microgrid is simulated using MATLAB/SIMULINK environment. The operation is carried out for the grid connected mode. Along with the hybrid microgrid, the performance of the doubly fed induction generator, photovoltaic system is analyzed. The solar irradiation, cell temperature and wind speed are also taken into consideration for the study of hybrid microgrid. The performance analysis is done using simulated results which are found using MATLAB.



Hybrid AC/DC Microgrid

4.1. Simulation of PV array

Figure (4.1) -(4.6) represents I-V, P-V, P-I characteristics with variation in temperature and solar irradiation. The nonlinear nature of PV cell is noticeable as shown in the figures, i.e., the output current and power of PV cell depend on the cell's terminal operating voltage and temperature, and solar irradiation as well.

Figures (4.1) and (4.2) verify that with increase of cell's working temperature, the current output of PV module increases, whereas the maximum power output reduces. Since the increase in the output current is much less than the decrease in the voltage, the total power decreases at high temperatures.




Fig 4.1. I-V output characteristics of PV array for different temperatures




Fig 4.2. P-V output characteristics of PV array for different temperatures




Fig 4.3. P-I output characteristics of PV array for different temperatures




Fig 4.4. I-V output characteristics of PV array for different irradiance levels




Fig 4.5. P-V characteristics of PV array for different irradiance levels




Fig 4.6. P-I characteristics of PV array for different irradiance levels

Figures (4.4) and (4.5) show that with increase of solar irradiation, the current output of PV module increases and also the maximum output power. The reason behind it is the open- circuit voltage is logarithmically dependent on the solar irradiance, however the short-circuit current is directly proportional to the radiant intensity.

4.2. Simulation of doubly fed induction generator

The response of wind speed, three phase stator voltage and three phase rotor voltage are shown in the figures (4.7) - (4.9). Here the value of wind speed varies between 1.0 to 1.05 pu which is necessary for the study of the performance of doubly fed induction generator. The phase-to-phase stator voltage is set to 300V whereas the rotor voltage value is 150V.




Fig 4.7. Response of wind speed




Fig 4.8. Three phase stator voltage of DFIG




Fig 4.9. Three phase rotor voltage of DFIG

4.3. Simulation results of hybrid grid

The various characteristics of the hybrid microgrid are represented by the figures (4.10) – (4.25). Here the microgrid operates in the grid tied mode. In this mode, the main converter operates in the PQ mode and power is balanced by the utility grid. The battery is fully charged. AC bus voltage is maintained by the utility grid and DC bus voltage is maintained by the main converter.

Figure (4.10) shows the curve of solar irradiation level which value is set as 950 W/sq.m from 0.0s to 0.1s, increases linearly to 1300 W/sq.m from 0.1s to 0.2s, remains constant from 0.3s to 0.4s, decreases to 950 W/sq.m and keeps that value until 1s. Figures (4.11) – (4.13) signify output voltage, current and power with respect to the solar irradiation signal. The output power of PV panel varies 11.25 kW to 13 kW, which closely follows the solar irradiation when the ambient temperature is fixed.




Fig 4.10. Irradiation signal of the PV array




Fig 4.11. Output voltage of PV array




Fig 4.12. Output current of PV array




Fig 4.13. Output power of PV array




Fig 4.14. Generated PWM signal for the boost converter




Fig 4.15. Output voltage across DC load

Figure (4.14) shows the gate pulse signal which is fed to the switch of boost converter. The output voltage across DC load is represented by figure (4.15) which is settled to around 820V.




Fig 4.16. State of charge of battery




Fig 4.17. Voltage of battery




Fig 4.18. Current of battery




Fig 4.19. Output voltage across AC load




Fig 4.20. Output current across AC load




Fig 4.21. AC side voltage of the main converter




Fig 4.22. AC side current of the main converter

The battery characteristics are shown in the figures (4.16) - (4.18). The state of charge of battery is set at 85% whereas the battery current varies between -50 to 50A and the value of battery voltage is nearly 163.5. The output characteristics of AC load voltage and current are represented by the figures (4.19) and (4.20). Phase to phase voltage value of AC load is 300V and current value is 50A. Figure (4.21) and (4.22) shows the voltage and current responses at the AC side of the main converter when the solar radiation value varies between 950-1300 W/sq.m with a fixed DC load of 25 kW.




Fig 4.23. Output power of DFIG




Fig 4.24. Three phase supply voltage of utility grid




Fig 4.25. Three phase PWM inverter voltage

Figure (4.23) shows the response of the DFIG power output which becomes a stable value 32kW due to mechanical inertia. Figure (4.24) and (4.25) represents the three-phase supply voltage to the utility grid and three phase PWM inverter output voltage respectively. In this chapter simulation results are discussed briefly. Also various characteristics of PV array, doubly fed induction generator, battery and converters are studied in this chapter and the waveforms are traced.

5. CONCLUSION & FUTURE SCOPE

Conclusion

The MATLAB/SIMULINK platform is used to simulate the hybrid microgrid power system setup. The focus of the current study is on the hybrid grid's grid-tied mode of operation. In order to keep the system stable under varying loads and resource circumstances, models are created for each of the converters, and their respective control mechanisms are investigated. The maximum power point tracking (MPPT) algorithm is used to get the most energy possible out of DC sources and to regulate the flow of electricity between the DC and AC grids. Although a hybrid grid may reduce the need for DC/AC and AC/DC converters within a single AC or DC grid, implementing a hybrid grid based on the existing AC dominant infrastructure presents a number of practical challenges. Reducing conversion losses and adding an additional DC connection will improve the overall system's efficiency. Electricity from the hybrid grid is more secure, of higher quality, and uses less resources than traditional grids. For tiny, remotely located manufacturing facilities, the hybrid grid might work if the primary power source includes photovoltaic cells and a wind turbine generator.

Future Scope

The control mechanism may be created for a microgrid with unbalanced and nonlinear loads; modelling can be done for the islanded mode of operation.

6. REFERENCES

- [1] Feng Gao; Xiaohui Wang; Peihao Yang; Shuichao Kou; Mengyao Sun "Research and Simulation of Hybrid AC/DC Microgrid" IEEE 2020 4th International Conference on HVDC (HVDC).
- [2] Lingfeng Kou; Xiaoyun Qu; Geng Niu; Baodi Ding "The Design Method of AC-DC Microgrid Based on Smart Energy Station" IEEE 2020 IEEE 4th Conference on Energy Internet and Energy System Integration (EI2).
- [3] Heng Du; Xuemeng Zhang; Qiuye Sun; Dazhong Ma "Power Management Strategy of AC-DC Hybrid Microgrid in Island Mode" IEEE 2019 Chinese Control and Decision Conference (CCDC).
- [4] Pengfei Tu; Shuhan Yao; Peng Wang; Lalit Goel "Hierarchical Reliability Modelling of an Islanded Hybrid AC/DC Microgrid" 2018 IEEE International Conference on Probabilistic Methods Applied to Power Systems (PMAPS).
- [5] Hao Zheng; Hongwei Ma; Kaiqi Ma; Zhiqian Bo "Modeling and analysis of the AC/DC hybrid micro-grid with bidirectional power flow controller" IEEE 2017 China International Electrical and Energy Conference (CIEEC).
- [6] A. A. Ejajal; Mohamed A. Abdelwahed; E. F. El-Saadany; Kumaraswamy Ponnambalam "A Unified Approach to the Power Flow Analysis of AC/DC Hybrid Microgrids" IEEE Transactions on Sustainable Energy (Volume: 7, Issue: 3, July 2016).
- [7] Wenjiao Guo; Xiaoqing Han; Chunguang Ren; Peng Wang "The control method of bidirectional AC/DC converter with unbalanced voltage in hybrid micro-grid" 2015 IEEE 10th

- Conference on Industrial Electronics and Applications (ICIEA).
- [8] Rahul Anand Kaushik; N. M. Pindoriya "Power flow control of hybrid AC-DC microgrid using master-slave technique" 2014 IEEE Conference on Energy Conversion (CENCON).
- [9] Nabil Qachchachi; Hassane Mahmoudi; Abdennebi El Hasnaoui "Optimal power flow for a hybrid AC/DC microgrid" IEEE 2014 International Renewable and Sustainable Energy Conference (IRSEC).
- [10] A. Mohamed; SriRajuBushanam Vanteddu; O. Mohammed "Protection of bi-directional AC-DC/DC-AC converter in hybrid AC/DC microgrids" 2012 Proceedings of IEEE Southeast con.
- [11] Poh Chiang Loh, Ding Li, and FredeBlaabjerg, "Autonomous Control of Interlinking Converters in Hybrid AC-DC Microgrid with Energy Storages," in IEEE Energy Conversion Congress and Exposition (ECCE), pp. 652-658, 2011.
- [12] Bo Dong, Yongdong Li, ZhixueZheng, Lie Xu "Control Strategies of Microgrid with Hybrid DC and AC Buses," in Power Electronics and Applications, EPE'11, 14thEuropean Conf., pp. 1-8,2011.
- [13] Xiong Liu, Peng Wang, and Poh Chiang Loh, "A Hybrid AC/DC Microgrid and Its Coordination Control," IEEE Trans. Smart Grid, vol. 2, no. 2, pp. 278-286 June.2011
- [14] MeiShan Ngan, Chee Wei Tan, "A Study of Maximum Power Point Tracking Algorithms for Stand-alone Photovoltaic Systems," in IEEE Applied Power electronics Colloquium (IAPEC), pp. 22-27, 2011.
- [15] Chi Jin, Poh Chiang Loh, Peng Wang, Yang Mi, and FredeBlaabjerg, "Autonomous Operation of Hybrid AC-DC Microgrids," in IEEE Int. Conf. Sustainable Energy Technologies, pp. 1-7,2010.
- [16] Dong Bo, YongdongLi , and Zedong Zheng, "Energy Management of Hybrid DC and AC Bus Linked Microgrid," in IEEE Int. Symposium Power Electronics for Distributed Generation System, pp. 713-716,2010.
- [17] A.Arulampalam, N. Mithulananthan, R.C. Bansal, and T.K. Saba, "Microgrid Control of PV -Wind-Diesel Hybrid System with Islanded and Grid Connected Operations," in Proc. IEEE Int. Conf. Sustainable Energy Technologies, pp. 1-5,2010.
- [18] S. N. Bhadra, D. Kastha, S. Banerjee, "Wind Electrical Systems," Oxford University Press, New Delhi, 2009.
- [19] Marcello Gradella Villalva, Jones Rafael Gazoli, and Ernesto Ruppert Filho, "Analysis and Simulation of the P&O MPPT Algorithm using a linearized PV Array model," in Industrial Electronics, IECON'09, 35th Annual Conf., pp. 189-195,2009.
- [20] M.E. Ropp and S. Gonzalez, "Development of a MATLAB/Simulink model of a single phase grid connected photovoltaic system," IEEE Trans. Energy Conv., vol. 24, no. 1, pp. 195-202, Mar2009.
- [21] Zhenhua Jiang, and Xunwei Yu, "Hybrid DC- and AC-Linked Microgrids: Towards Integration of Distributed Energy Resources," in IEEE Energy2030 Conf., pp.1-8,2008
- [22] D. Sera, R. Teodorescu, J. Hantshel, and M. Knoll, "Optimized maximum power point tracker for fast-changing environmental conditions," IEEE Trans. Ind. Electron., vol.55, no. 7, pp. 2629-2637, Jul. 2008.
- [23] O. Tremblay, L. A. Dessaint, and A. I. Dekkiche, "A generic battery model for the dynamic simulation of hybrid electric vehicles," in Proc. IEEE Veh. Power propulsion Conf., pp. 284-289, 2007.
- [24] H.Nikkhajoei, R. H. Lasseter, "Microgrid Protection," in IEEE Power Engineering Society General Meeting, pp. 1-6, 2007.
- [25] M. Barnes, J. Kondoh, H. Asano, and J. Oyarzabal, "Real-World MicroGrids- an Overview," in IEEE Int. Conf. Systems of Systems Engineering, pp.1-8,2007.
- [26] S. Bose, Y. Liu, K. Bahei-Eldin, J.de Bedout, and M. Adamiak, "Tie line Controls in Microgrid Applications," in iREP Symposium Bulk Power System Dynamics and Control VII, Revitalizing Operational Reliability, pp. 1-9, Aug.2007.
- [27] N.Kroutikova, C. A. Hernandez-Aramburo, and T. C. Green, "State-space model of grid connected inverters under current mode control," IET Elect. Power Appl., vol. 1, no. 3, pp. 329-338, 2007.
- [28] F. Katiraei and M. R. Iravani, "Power Management Strategies for a Microgrid with Multiple Distributed Generation Units," IEEE trans. Power System, vol. 21, no. 4, Nov. 2006.

- [29] P. Piagi and R. H. Lasseter, "Autonomous control of microgrids," in Proc. IEEE-PES'06, 2006, IEEE, 2006.
- [30] Michael Angelo Pedrasa and Ted Spooner, "A Survey of Techniques Used to Control Microgrid Generation and Storage during Island Operation," in AUPEC, 2006.
- [31] B. Bryant and M. K. Kazimierczuk, "Voltage loop of boost PWM DC-DC converters with peak current mode control," IEEE Trans. Circuits Syst. I, Reg. Papers, vol. 53, no. 1, pp. 99-105, Jan. 2006.
- [32] F. D. Kanellos, A. I. Tsouchnikas, and N. D. Hatziaargyriou, "Microgrid Simulation during Grid-Connected and Islanded Mode of Operation," in Int. Conf. Power Systems Transients (IPST'05), June. 2005.
- [33] Y. Ito, Z. Yang, and H. Akagi, "DC Microgrid Based Distribution Power Generation System," in Proc. IEEE Int. Power Electron. Motion Control Conf., vol. 3, pp. 1740-1745, Aug. 2004.
- [34] Y. Zoka, H. Sasaki, N. Yomo, K. Kawahara, C. C. Liu, "An Interaction Problem of Distributed Generators Installed in a MicroGrid," in Proc. IEEE Elect. Utility Deregulation, Restructuring and Power Technologies, pp. 795-799, Apr. 2004.
- [35] Y. W. Li, D. M. Vilathgamuwa, and P. C. Loh, "Design, analysis, and real-time testing of a controller for multi bus microgrid system," IEEE Trans. Power Electron., vol. 19, pp. 1195-1204, Sep. 2004.
- [36] R. H. Lasseter and P. Paigi, "Microgrid: A conceptual solution," in Proc. IEEE- PESC'04, pp. 4285-4290, 2004.
- [37] Mesut E. Baran, and Nikhil R. Mahajan, "DC Distribution for Industrial Systems: Opportunities and Challenges," IEEE Trans. Industry Applications, vol. 39, no. 6, pp. 1596-1601, Nov/Dec. 2003.
- [38] R. H. Lasseter, "MicroGrids," in Proc. IEEE-PES'02, pp. 305-308, 2002.
- [39] Mohammad A. S. Masoum, Hooman Dehbonei, and Ewald F. Fuchs, "Theoretical and Experimental Analyses of Photovoltaic Systems with Voltage- and Current-Based Maximum Power-Point Tracking", in IEEE Trans. Energy Conversion, vol. 17, no. 4, pp. 514-522, Dec. 2002.
- [40] B. K. Bose, "Modern Power Electronics and AC Drives," Prentice-Hall, Inc., New Delhi, 2002.
- [41] S. Arnalte, J. C. Burgos, and J. L. Rodriguez-amenedo, "Direct torque control of a doubly fed induction generator for variable speed wind turbines," Elect. Power Compon. Syst., vol. 30, no. 2, pp. 199-216, Feb. 2002.
- [42] A. Girgis and S. Brahma, "Effect of Distributed Generation on Protective Device Coordination in Distribution System," in Large Engineering Systems Conf. Power Engineering, pp. 115-119, 2001.
- [43] D. P. Hohm, M. E. Ropp, "Comparative Study of Maximum Power Point Tracking Algorithms Using an Experimental, Programmable, Maximum Power Point Tracking Test Bed", in IEEE, pp. 1699-1702, 2000.
- [44] R. Pena, J. C. Clare, G. M. Asher, "Doubly fed induction generator using back to back PWM converters and its application to variable speed wind energy generation," in Proc. IEE Electr. Power Appl., vol. 143, no. 3, pp. 231-241, May 1996.
- [45] K. H. Hussein, I. Muta, T. Hoshino, and M. Osakada, "Maximum Photovoltaic Power Tracking: An Algorithm for rapidly changing atmospheric conditions," in Proc. Inst. Elect. Eng. Gener. Transm. Distrib., vol. 142, pp. 59-64, Jan. 1995.